MIDCO
DIVING & MARINE SERVICES

September 28, 2026

Pleasant Valley School District
Attn: Randy Smale
477 Polk Twp. Road
Kunkletown, PA 18058

RE: 2026 Tank Maintenance Project

Thank you for considering Midco Diving & Marine Services, Inc. – a proud member and supporter of the National Rural Water Association (NRWA). We are pleased to provide the following proposal to perform the scope of work outlined below.

All diving operations are fully insured for **"Commercial Diving Operations"** including: General Liability, Workman's Compensation, Hull Machinery, Protection and Indemnity, Pollution Liability, Maritime Employer's Liability, Contractor's Pollution, Automotive Liability, U.S.L.H., and Umbrella/Excess Liability/Bumbershoot. **Verifiable Certificates of Insurance with Current Limits** are available upon request.

Midco Diving & Marine Services, Inc. is in full compliance with OSHA 29 CFR 1910, Subpart T – Commercial Diving Operations regulations. OSHA specifies that the minimum acceptable dive crew size is three qualified divers. Not all firms comply with this mandate and continue to use two-person dive crews or unqualified personnel; please be aware of the safety concerns when evaluating our proposal.

Current diver and equipment certifications will be available on-site for review:

Diver training – from an accredited commercial dive school (each dive team member)
Current First Aid/CPR training (each dive team member)
Annual medical examination determining diver is fit to perform assigned tasks (each dive team member)
Air purity test for breathing air source(s) – tested every 6 months
Breathing gas supply hoses – tested at least annually to 1.5 times their working pressure
Depth gauges – calibrated every 6 months

TANK DESCRIPTION(S) & SCOPE OF WORK

(See Page 3)

Inspection

The diver inspection with a live video recording will be transferred to a flash drive documenting our findings in each tank(s). Inspection procedures include, but are not limited to:

- Inlet / Outlet
- Overflow
- Roof and Roof Hatch
- Walls and Floors
- Baffles / Support Walls
- Interior Ladders
- Roof Vents
- Exterior Ladder & Rails
- Sumps
- Internal Plumbing
- Joints & Seams
- Telemetry
- Interior Coatings
- Exterior Coatings
- Sediment Depths
- Thermal Stratification
- Bio-film Buildup
- Passive / Active Mixers

Cleaning

Midco will remove up to three inches **(3")** of accumulated material from the storage tank floor using underwater vacuum procedures as needed. Material(s) that cannot be removed by normal vacuum procedures or material(s) in excess of three inches (3") will be removed for an **additional charge** with an estimated price given on site. Material(s) such as sand, gravel, and concrete are considered debris and will be removed by hand at an **additional charge**. All discharged materials, including water, are the responsibility of the Client, Owner, or Owners Representative unless prior arrangements are made.

Potable Water Operations – All Midco divers and associated in-tank equipment are fully disinfected in accordance with ANSI/AWWA Standard C652-19. All system entries will be conducted in accordance with applicable OSHA regulations pertaining to Diving & Confined Space; including 1910.401 – 1910.441. Specialty equipment may include but is not limited to; appropriate OSHA climbing and personal fall protection, AWWA, and ADCI-approved commercial diving equipment as it relates to in-service potable water operations.

MIDCO
DIVING & MARINE SERVICES

Cleaning & Inspection (Includes Inspection Video)	**$4,678.00**
Repairs	**$565.00/Hr.**

NOTE: Pricing to Include Setup, Breakdown, and Materials

Additional Services

☑ **Emergency Mobilization/Demobilization Rate**	**$2,876.00**
☐ **Confidential Report Utilizing EPA Guidelines**	**$396.00 Each**
☑ **Confidential Full Written Report Utilizing EPA or State Guidelines**	**$545.00 Each**
☐ **No Report(s) Requested**	

Pricing above does not include Local, State or Franchise Taxes – if any.
Additional Fees may be applied upon receipt of any Contract post-proposal acceptance as required.

This proposal, when executed by both parties, shall constitute a binding agreement between the parties. The persons signing on behalf of the Client, Owner, or Owners Representative and Midco hereby represents and certifies that they are fully empowered to bind the respective parties to this contract. Any contract that is not fulfilled will be subject to a cancellation fee. **Terms are net 10 days from completed on-site work**; interest accrues at 1.5% monthly on any unpaid balance. Any fees required to obtain a city business license or any additional permits will be added to the final invoice at the current city rate plus appropriate markup. Please note the above pricing **does not include**; contract review, comprehensive dive plans, additional insurance requirements, third-party vendor verification site requirements, and/or any repair work unless stated with the above pricing. This proposal is valid for thirty (30) days from receipt.

To expedite your project please be aware of the following:

- The tank(s) must be full to overflow and in-service prior to the crews' arrival. In order to ensure diver safety, the headspace or air gap cannot exceed 5' from the access hatch regardless of overflow elevation.
- Access into the reservoirs must be sufficient for safe diver entry and exit. A minimum hatch size of 24" in diameter, no hatch obstructions, and unobstructed road access to the tank is required.
- Project sites and structures must comply with OSHA Standards & Regulations (i.e. weight-rated tie off points, guardrails, etc.)
- Working with our scheduling department to complete the project in a timely and proficient manner, which may require weekend and/or holiday access.
- It will be the responsibility of the Client, Owner, or Owner Representative to notify antenna operator and/or owners prior to crews' arrival for proper lockout of all antennas, RF devices (Radio Frequency Antennas) and EME sources (Electromagnetic Energy) that may interfere with Midco team safety and access to the water reservoirs.

This quote has been prepared exclusively for your firm using the information you provide. Incorrect or inaccurate information used for estimate purposes that delays progress may influence your final price. The client is responsible for all-weather access for Midco crew(s) and equipment. Any damages related to tank and/or site location(s) because of poor site conditions, (ex. snow, rain, mud, etc.) and obstructed road access may result in additional fees and/or a nominal trip charge to be applied to the final invoice. Interruptions in the work progression, not in control of Midco Diving & Marine Services, Inc., such as weather or other delays may also affect your final pricing. Every attempt will be made to conduct services in a safe manner & in accordance with OSHA standards & regulations. If Midco Diving & Marine Services, Inc. is unable to complete the work as described above due to lack of weekend and/or holiday access, tank access, non-compliance with OSHA standards & regulations at project sites/structures, water levels, safety issues, etc. a nominal trip charge and/or standby fee will be added. The contents of this quotation are considered confidential and are not to be divulged to third parties. Please note, it is the Client, Owner, and Owner Representative's responsibility to test and maintain for water quality.

All Midco Diving quotes are subject to the availability of personnel and equipment. Upon approval, please sign and return by fax, email, or mail to Midco Diving & Marine Services, Inc.

Pleasant Valley School District
Attn: Randy Smale
477 Polk Twp. Road
Kunkletown, PA 18058

Midco Diving & Marine Services, Inc.
PO Box 513
Rapid City, SD 57709
P: (800) 479-1558 / F: (800) 238-0217

I have read, understand, and agree to the terms of this proposal:

By: James A. Konrad

Title: Superintendent

Date: 9/28/26

By: Alec Sommers

Title: Pennsylvania Regional Account Manager

Date: September 28, 2026

MIDCO
DIVING & MARINE SERVICES

TANK DESCRIPTION(S)

Tank	Capacity	Dimensions	Type
Pleasant Valley School Tower	90K Gallons	80' Height x 14' Diameter	Standpipe / Steel Bolted

SCOPE OF WORK

1. Midco dive crew will complete NSF-approved epoxy repairs, beginning with the most severe areas first.
2. Midco dive crew will go down approximately 15' to locate the 2" hole at the bolted joint to complete repairs.
3. Repair work will be performed at an hourly rate, at the direction of Pleasant Valley School District.

The repair work will be documented on video, but no additional inspection and/or reporting will be completed. While Midco Diving & Marine Services, Inc. has had great success with repair work, the repairs are not guaranteed.

800.479.1558 (P)
800.238.0217 (F)
605.791.3030 (O)
www.midcodiving.com / info@midcodiving.com
PO Box 513, Rapid City, SD. 57709